

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T 48 NR 15 W

A l g e r COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sections 5 and 6

DESCRIPTION OF CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap

WITNESSES TO CORNER 10" Red Pine (1/4s NBT) N 46° E 22 Links

11" Red Pine (1/4s NBT) S 30° W 50 Links

7" W. Pine (1/4s NBT) S 84° E 67 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by single proportionate measure and on line between two Sections corners. No evidence of original corner. Corner lies one chain north of road.

Corner was placed and witnessed June 21, 1960 with Russell Hind.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 7/21/60
REGISTERED LAND SURVEYOR
Billy D. Buckler