

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. ~~47-48~~ NR. 15 W

Alger COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sections 2 and 35

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 8" W. Pine (1/4s NBT) N 10° W 157 Links

18" W. Pine Stub (1/4s NBT) S 10° E 111 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established midway and on line between two Section Corners. No evidence of original corner. Corner lies at end of road from east.

Corner was placed and witnessed June 23, 1960 with Russell Hinds.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 7/27/60  
REGISTERED LAND SURVEYOR  
Billy D. Buckler