

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 48. NR. 15. W

Alger COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sections 21 and 22

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 28" W. Pine Stump (1/4s NBT) S 25° W 45 Links

30" W. Pine Stump (1/4s NBT) S 74° E 99 Links

14" W. Pine Stub (1/4s NBT) N 6° E 160 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. This corner was re-established by single proportionate measure between

Meander Corner 49.81 Chains to north and a W. Pine Line Tree 8.75 Chains south.

Found this entire distance to be 02 Links longer than record distance. This line tree is still standing though badly burned. Notches are very plain.

Corner was placed and witnessed June 15, 1960 with Russell Hinds.

SURVEYORS SEAL

SIGNED

*Billy D. Buckler*  
REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 7/21/60