

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48. NR. 15. W.

Alger COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sections 21 and 28

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 40" W. Pine Stump (1/4s NBT) S 15° E 80 Links

40" W. Pine Stump (1/4s NBT) S 85° E 64 Links

40" W. Pine Stump (NBT) North 09 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was re-established midway and on line between two Section corners. Found W. Pine Stump 9 Links north with numerous blazes and notches but no evidence of Hemlock bearing tree.

Corner was placed and witnessed June 15, 1960.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 7/2/60