

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48. NR. 15-16 W

A l g e r COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sections 1 and 6

DESCRIPTION OF CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap

WITNESSES TO CORNER 16" W. Pine Stub (1/4s NBT) N 67° W 54 Links

36" W. Pine Stump (NBT) N 10° W 25 1/2 Links

22" W. Pine Stump (NBT) S 43° W 47 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by single proportionate measure between two section corners. No evidence of original corner. Corner lies in line with road to north and 15 Links south of road to west.

Corner was placed and witnessed June 21, 1960 with Russell Hinds.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 7/21/60
REGISTERED LAND SURVEYOR
Billy D. Buckler