

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION



LAND CORNER RECORD

T. 48. NR. 15. W.

Alger COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sections 15 and 22

DESCRIPTION OF CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap

WITNESSES TO CORNER 30" W. Pine Stub (1/4s NBT) S 61° W 85 Links

16" W. Pine (1/4s NBT) S 7° E 140 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by proportionate measure between Section corner to east and Meander Corner to west. No evidence of original corner. Corner lies in west wheel track of N. - S. Road. Note: Monument lies 03 Links west of true 1/4 corner.

Corner was placed and witnessed June 21, 1960 with Russell Hinds.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 7/21/60  
REGISTERED LAND SURVEYOR  
Billy D. Buckler