

SURVEY & REMONUMENTATION

FEB 19 1998

Approved by Alger County Land Survey Remonumentation Peer Group Under Act 345 of P.A. of 1990 On 12-10-1997

SECTION

05-92

Donald W. Kinnunen
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____ (County)	Located In:	Corner Code #
	48 16	E12
1. Public Land Survey	T <u>35</u> R <u>16</u>	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILE
TIME 8:30 Am

DEC 17 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Jamros, in a field survey on June 10, 1997, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E12: PLS - William Ives, 09, 1850 * Set quarter section post * Beech 10, S.53 E., 55 links * Maple 7, N.20 W., 33 links **** No other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Established a corner position by survey and made a search for GLO corner evidence, search inclusive. Area is mostly young timber and has been frequently cut over. Established corner position on true line at midpoint between section corners North and South * Installed monument and made 4 reference trees * Corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E12: Set Bernsten Monument No. A1N830, stamped to identify corner position. Established reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measure w/Alum. I.D washers in the following reference trees - Maple 10, N.50 1/2 E., 22.46 feet, '1/4S BT' * Maple 6, S.53 E., 24.51 feet, '1/4S BT' * Beech 16, S.27 W., 27.65 feet, '1/4S BT' * Maple 3, N.61 W., 30.17 feet, not scribed. * Survey marker sign on 6 foot steel post, N.33 E., 1.0 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12/10/1997

