

FEB 19 1998

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12-10-1997

SECTION

05-91

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in \_\_\_\_\_

(County)

Located In:

Corner Code #

- |                                      |   |           |   |           |       |
|--------------------------------------|---|-----------|---|-----------|-------|
| 1. Public Land Survey                | T | <u>48</u> | R | <u>16</u> | F11   |
|                                      | T | _____     | R | _____     | _____ |
|                                      | T | _____     | R | _____     | _____ |
|                                      | T | _____     | R | _____     | _____ |
| 2. Property Controlling in Section   | S | _____     | T | _____     | R     |
|                                      | S | _____     | T | _____     | R     |
| 3. Miscellaneous Property in Section | S | _____     | T | _____     | R     |
|                                      | S | _____     | T | _____     | R     |

FILED  
TIME 8:30 A.M.

DEC 17 1997

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Jamros, in a field survey on June 04, 1997, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

F11: PLS - William Ives, DS, 1850 \* Set quarter post \* Sugar 5, S.55 W., 19 links \* Sugar 7, N.10, W., 22 links \*\*\*\* P.D. Brotherton, RLS, 1948 \* Set 3 inch iron spring leaf \* Government Sugar 8T here, N.10 W., 22 links, good shape \* stump only on the Government BT, S.55 W., 19 links \* Iron is flush w/rocks packed around top \* Witnesses - \*Maple 2, S.15 W., 34.6 feet \* Maple 8, N.05 W., 52.6 feet \* Unrecorded report \*\*\*\* No other subsequent restoration.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 3 inch iron spring leaf with rocks packed around \* 16 inch Maple stump w/lower blaze scar, N.05 W., 52.6 feet \* Set new monument at corner position of spring leaf and established reference trees \* Corner position as found is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

F11: Set Berntsen Monument No. 419300 adjacent to leaf spring, stamped to identify corner position \* Established reference trees w/BT signs, blazed, scribed and painted \* Set PK nails for measure w/Alum. I.O. washers in the following reference trees - Maple 12, N.56 W., 1.77 feet, '1/4BT' \* Maple 11, S.57 E., 32.03 feet, '1/4BT' \* Maple 8, S.41 E., 16.19 feet, '1/4BT' \* Maple 8, S.39 W., 34.10 feet, '1/4BT' \* Survey marker sign on 1 foot steel post, S.13 W., 1.3 feet. \* All bearing are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date 12/10/1997

