

Approved by Alger County
Land Survey Professional Commission
Peer Group Under Act 1361
P.A. of 1990 On 3-24-1997

Gerald Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

5-14

For corners in ALGER - SCHOOLCRAFT Located In: Corner Code #
(County)

FILED
TIME 2:00 p.m.

MAR 31 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

1. Public Land Survey T 48N R 16W F13
T 47N R 16W F1
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 6 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

T47N. R.16W. F1 Schoolcraft Co.

I, Robert L. Jamros, in a field survey on June 07, 1996, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F13: PLS - William A. Burt, DS, 1841, Set quarter Section post * Beech 9, N.13 E., 52 links * Beech 9, N.13 W., 26 links **** No other subsequent restoration found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F13: Found 20" dead Beech stub (15' high) in N.13 W. GLO position. Old blaze scars around tree at eye level. GLO blaze scar open and deep with portions of measuring notch still visible. Set corner position at S.13 E., 26 links from GLO measuring notch. There is a 12" Maple paint marked 1/4 S approx. 8 feet southerly of corner position w/ blaze lines running East and West. This corner position was recovered during the Section Subdivision Survey of Section 4, T.47N., R.16W. Monument as set is accepted as a careful and faithful perpetuation of the position of the original corner.

SURVEY & REMONUMENTATION

AUG 15 1997

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F13: Set Berntsen Monument No. A1NB30, stamped to identify corner position. Established reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure w/ Alum. I.O. washers in the following reference trees. * Maple 16", S.64 W., 18.93 feet, * 1/4S BT * Maple 12", N.30 W., 13.23 feet, * 1/4S BT * Maple 6", N.67 E., 26.54 feet, * 1/4S BT * Maple 5", S.21 E., 28.73 feet, * 1/4S BT * Survey marker sign on six foot steel post, S.44 E., 1.0 feet. * All bearings are magnetic.

Signed by

Robert L. Jamros

Date 25 March, 1997

Surveyor's Michigan License No.

25849



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983