

FEB 19 1998

SECTION

Approved by Alger County
Land Survey Re-monumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12-10-1997

05-90

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Yweid C. Kales
Chairman

For corners in _____

(County)

Located In: _____

Corner Code # _____

- | | | | | | | |
|--------------------------------------|---|-----------|---|-----------|------------|-------|
| 1. Public Land Survey | T | <u>48</u> | R | <u>16</u> | <u>411</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

FILED
TIME 8:30 A.M.

DEC 17 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Jamros, in a field survey on June 11, 1997, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

311: PLS - William Ives, OS, 1850 * Post set corner of Sections 27, 28, 33 & 34 * Sugar 11, S.70 E., 11 links * Beech 8, N.58 W., 21 links **** H.C. Lawrence, RLS, 1953 * Set scribed 6 inch post from original BT, Beech 8, N.58 W., 21 links * Witnesses - Sugar 8, N.70 1/4 E., 14.5 feet * Beech 9, S.12 E., 22.5 feet * Unrecorded **** Robert L. Jamros, RLS, 1991 * Recovered post point of down wood post * Found Beech stump with scribing at a distance of 21 links from post point * Set 1/2 inch by 18 inch iron bar w/I.D. cap in place of post point * Witnesses - Beech 13, S.66 E., 14.66 feet * Maple 14, N.23 W., 32.48 feet * Maple 12, N.78 E., 22.56 feet * Maple 7, S.54 E., 27.78 feet * Recorded in Liber 1, Page 406, Alger County corner records **** No other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2 inch iron bar w/I.D. cap * Recovered 2 exist. BT's of the 1953 unrecorded report and the 1991 record report, all others have been cut down * Installed new monument, renewed exist. BT's and established additional reference trees. * Corner position as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

311: Set Bernstein Monument No. A1N830, stamped to identify corner position. Established reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measure w/Alum. I.D. washers in the following reference trees - Exist. Beech 16, S.07 E., 14.66 feet, dbl. blzd. * Beech 7, S.30 W., 18.25 feet, '333 BT' * Exist. Maple 22, N.24 W., 32.37 feet, dbl. blzd. * Beech 3, N.64 E., 21.46 feet, '333 BT' * Survey marker sign on 6 foot steel post. S.34 E., 0.90 feet * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12/10/1997

