

DEC 27 1999

Approved by Alger County Land Survey Remonumentation Peer Group Under Act 245 of P.A. of 1990 On 12-8-99

Harold Watson
Chairman

For corners in SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-153

	Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 15W	A10	
	T 48N R 16W	M10 ✓	
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		

FILED
TIME 1:30 pm.

DEC 15 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on September 25, 1999, 19____, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A10: PLS * William A. Burt, DS, 1841. * Set quarter section post. * Beech 14', N.12 E., 19 links. * Beech 6', N.25 W., 49 links. * No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A10: Located corner search area by calculated position and standard field survey. Made search for GLO BT's, references destroyed and lost. Area heavily logged off many times. Established corner position at proportional distance and on line between section corner 1/2 mile North and the meander corner to the South on the North shore of Nevin's Lake. Corner position as established is a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A10: Set 2 1/2"x30" Berntsen aluminum monument No. A1NB30 with 3 1/4" aluminum cap stamped to identify corner position. * Established the following reference trees with BT signs, blazed, scribed and painted. * Set PK nails with aluminum I.D. washers for measure in the following: Beech 4", N.63 E., 14.46 feet, '1/4s BT'. * Maple 6", S.71 E., 21.40 feet, '1/4s BT'. * Beech 5", S.66 W., 20.76 feet, '1/4s BT'. * Maple 8", N.62 W., 31.81 feet, '1/4s BT'. * Survey marker sign on 6 foot steel post, S.53 W., 1.5 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date Dec 15 1999

