

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48 N.R. 16-17W


ALGER COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 30, 31, 25, 36

CORNER MONUMENT 1" pipe 3 1/2' long.

DATE MONUMENT PLACED AND WITNESSED 8/11/60

WITNESSES TO CORNER..... 6" Soft Maple (S 30 NBT) N 30° E 28 Links


6" Soft Maple (S 36 NBT) S 51° W 28 1/2 Links

AND

7" Soft Maple (S 25 NBT) N 64° W 17 Links

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measure. No evidence of original corner. Pipe buried in west wheel track of dirt road, NW & SE, about 8" below ground level.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 5/23/61
REGISTERED LAND SURVEYOR
Billy D. Buckler