

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Alger	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 48N R 16W	L3
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 12 T 48N R 16W	7
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11				
5													
6	18		17		16		15		14				
7													
8	19		20		21		22		23				
9													
10	30		29		28		27		26				
11													
12	31		32		33		34		35				
13													

I, Stephan J. Szyszkoski, in a field survey on L3 11/12/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(L3) Quarter corner common to Sections 1 and 12. 1850 - Established by Wm. Ives, Deputy Surveyor, midway and on the Section line between Section corners 40.11 chains east and west. Set Quarter section post. Maple 6 N53E 4 links, Y.Birch 6 S48W 13 links. Found no subsequent record.

(7-Sec. 12) North 1/16 corner between Section 12 T48N-R16W and Section 7 T48N-R15W. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(L3) The original post and accessories were not recovered. At a position S3E 9.8' from the position proportionate to the original record, I found an old squared and scribed wooden post, set by persons unknown. At very nearly record bearing and distance from this post, I found a Maple 12" N55E 3.2' and a Y.Birch 15" S57W 8.2' distant. These trees match the original bearing tree species and both show old rotted out blazes at BH and root crown which would correspond to the original markings. However, these trees appear to be too young to be the originals. I accept the location of the wood post as the best available evidence of the position of the original corner and replace it with a monument as described below.

(7-Sec. 12) Established the corner midway and on the Range line between Section corner 1322.57' north and Quarter corner 1322.57' south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(L3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 6" Hemlock N07W 1.45' mrkd "1/4S NBT"  
 7" Hemlock S25E 1.24' do  
 6" Hemlock N52E 2.49' do  
 7" Hemlock S65W 15.97' do  
 Bearings are magnetic.

(7) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 13" Maple N26W 4.6' mrkd "N1/16 BT"  
 10" Hemlock N77W 35.25' do  
 13" Maple S24E 15.9' do  
 8" Maple S88E 15.7' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 05/07/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

