

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T 48N R 16W T _____ R _____	_____ L1 _____
2. Property Controlling in Section	S 2 T 48N R 16W S _____ T _____ R _____ S _____ T _____ R _____	_____ 2 _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims	2 04/07/2009	

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on L1 10/28/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(2-Sec. 2) East 1/16 corner between Section 2 T48N-R16W and Section 35 T49N-R16W. Not established in the original survey.

(L1) Quarter corner common to Section 1 T48N-R16W and Section 36 T49N-R16W. 1841 - Established by Wm.A.Burt, Deputy Surveyor. Set post. W.Pine 30" N65E 24 links, W.Pine 14" N35W 18 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(2) Established the corner midway and on the Township line between Quarter corner 1321.81' West and Section corner 1321.81' East.

(L1) The original post was not recovered. At a position S78E 3.2' from the position midway between Section corner to west and Township corner to east, I found an old axle, set flush with the ground, at record bearing and distance from the stump remains of two W.Pines, no markings found, possibly the remains of the original BTs. Accepted the axle as the best available evidence of the position of the original corner. Removed the axle and replaced it with a monument as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(2) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 14" Maple N03W 0.58' mrkd "E1/16 BT"
 13" Maple S52W 15.7' do
 5" Maple S18W 20.37' do
 6" Hemlock S41E 57.0' do
 The monument is adjacent to the 14" Maple and is leaning to the north. The top center of the cap marks the corner position. Brgs magnetic.

(L1) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 11" R.Pine S58W 57.44' mrkd "1/4S NBT"
 7" W.Pine N66W 34.65' do
 14" R.Pine S85E 66.5' do
 7" R.Pine S60E 83.26' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 05/07/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

