

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Alger	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 48N R 16W	J1
	T 48N R 16W	K1
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on J1 10/15/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(J1) Quarter corner common to Section 2 T48N-R16W and Section 35 T49N-R16W. 1948 - Reestablished by Ray J. Brotherton RLS midway between Section corners I1 and K1 and on a straight line between K1 and a positively identified Hemlock Line tree west of K1. Set 4" squared fir post. 9" Sugar N40W 17.9', 6" Beech S61E 17.7'. 6.34 chains west of the 1/4 to Log Road course N30E.

(K1) Corner common to Sections 1-2 T48N-R16W and Sections 35-36 T49N-R16W. 1948 - Perpetuated by Ray J. Brotherton RLS in the remains of a notched and burnt pine stump judged by Mr. Brotherton to be the remains of the original Gov't corner tree. No description of new monumentation was given.  
 Witnesses: 12" Norway Pine S15E 61 links, 11" Norway Pine N01E 36.5 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(J1) The 1948 post was not recovered. Found the 1948 witnesses and at record bearing and distance, recovered the corner post hole in the ground. Also found, adjacent to the hole, a 3/4" dia. iron pin and a 5/8" rebar, set by persons unknown. Accepted the location of the post hole and NBTs as a careful and faithful reestablishment of the position of the original corner and drove a new monument, described below, into the post hole.

(K1) Found the remains of the burnt pine stump noted in the 1948 record, at record bearing and distance from the 1948 witness trees, both in good condition with overgrown blazes. Found an old squared post, rotted off and laying on the ground, adjacent. Recovered the post hole of this post in the center of the stump and drove a new monument at that position.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(J1) Set 1"IDx36" I.pipe with plastic cap stamped "MI DNR LS33986". Set measuring nail with MDNR tag in the side of:  
 18" Sugar N31W 17.88' mrkd "1/4S NBT" 1948 NBT  
 7" Maple N86E 27.41' do  
 19" Maple S38E 29.35' do  
 6" Maple N30E 24.17' do  
 Bearings are magnetic.

(K1) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 10" R.Pine N30E 4.94' mrkd "S36 NBT"  
 12" W.Pine N50W 27.22' "S35 NBT"  
 10" W.Pine S83W 24.82' "S2 NBT"  
 20" R.Pine S11E 40.82' mrkd "S1 NBT" 1948 NBT

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 05/07/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities