

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Alger	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 48N R 16W	M2
	T 48N R 16W	M4
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on M2 09/09/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M2) Quarter corner common to Section 1 T48N-R16W and Section 6 T48N-R15W. 1960 - Reestablished by single proportionate measurement to the original GLO record by Billy D. Buckler RLS. Set 1" iron pipe with 4" brass cap. 16" W.Pine stub N67W 54 links, 36" W.Pine stump N10W 25.5 links, 22" W.Pine stump S43E [erroneously noted as S43W in the record] 47 links.

(M4) Quarter corner common to Section 12 T48N-R16W and Section 7 T48N-R15W. 1951 - Remonumented from Gov't Bearing Tree by Ray J. Brotherton RLS. Set post. 4" Beech S46 1/2W 35.5 links, 10" Maple N15 1/2E 37.5 links. Down Gov't BT Hemlock is N08E 22 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M2) Recovered the 1960 monument in good condition and at record bearing and distance from two of the three 1960 witness trees, found in good condition. The W.Pine stub NW was not recovered. I found the position of the monument to be substantially in accord with the record. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

(M4) Found the rotted remains of the 1951 post point in the ground and at record bearing and distance from the 1951 NBTs and the Hemlock BT, now a rotting stump. Accepted the position of the post point as a careful and faithful perpetuation of the position of the original corner. Drove a new monument at that position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M2) Fd. 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 6" W.Pine S63W 39.1' mrkd "1/4S NBT"
 8" W.Pine S20E 39.98' do
 9" R.Pine S50E 55.34' do
 9" R.Pine N48W 59.4' do
 Bearings are magnetic.

(M4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 16" Maple N22E 24.95' mrkd "1/4S" 1951 NBT
 8" Hemlock N66W 20.35' mrkd "1/4S NBT"
 12" Hemlock S57W 36.25' do
 11" W.Pine S27E 9.7' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski Date 05/07/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

