

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Alger	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>1</u> T <u>48N</u> R <u>16W</u>	<u>3</u>
	S <u>1</u> T <u>48N</u> R <u>16W</u>	<u>5</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 3 11/03/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(3-Sec. 1) North 1/16 corner between Sections 1 and 2. Not established in the original survey.

(5-Sec. 1) North 1/16 corner, Section 1. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(3-Sec. 1) Established the corner on the Section line between Quarter corner 1322.45' south and Section corner 1337.65' north, being 20.01 chains, proportionate to the original record, north of the Quarter corner.

(5-Sec. 1) Established the corner on a straight line between Center of Section 1323.01' south and Quarter corner 1338.21 north, being proportionate to the dimensions given on, and derived from, the original government plat of this township.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 13" W.Pine S28E 9.19' mrkd "N1/16 BT"
 12" Spruce N62W 20.82' do
 11" W.Pine S08W 13.84' do
 10" Maple S37W 26.85' do
 Bearings are magnetic.

(5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 13" R.Pine S31W 22.75' mrkd "N1/16 BT"
 11" R.Pine West 23.8' do
 23" W.Pine N14E 37.75' do
 9" R.Pine N74E 54.15' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 05/07/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

