

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S <u>1</u> T <u>48N</u> R <u>16W</u>		<u>E-W 1/64</u>
	S <u>1</u> T <u>48N</u> R <u>16W</u>		<u>C-E-SW 1/64</u>
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11				
5													
6	18		17		16		15		14				
7													
8	19		20		21		22		23				
9													
10	30		29		28		27		26				
11													
12	31		32		33		34		35				
13													

I, Stephan J. Szyszkoski, in a field survey on 11/05/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E-W 1/64) 1/64 corner on the Section line West of L3, being the SW corner of the E1/2 of the SE1/4 of the SW1/4 of Section 1. Not established in the original survey.

(C-E-SW 1/64, Sec. 1) 1/64 corner being the NW corner of the E1/2 of the SE1/4 of the SW1/4 of Section 1. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-W 1/64) - Established the corner midway and on the Section line between Quarter corner 663.44' East and 1/16 corner #15 (Sec. 1) 663.44' West.

(C-E-SW 1/64) Established the corner midway and on a straight line between 1/16 corners #11 and #12, 662.40' west and east, respectively.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-W 1/64) Set 1"IDx36" I.pipe w/4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 17" twin Hemlock N05E 11.93' mrkd "1/64 BT"
 9" Hemlock S55E 26.1' do
 16" Hemlock N52W 24.93' do
 20" Hemlock S75W 30.93' do
 Bearings are magnetic.

(C-E-SW 1/64) Set 1"IDx36" I.pipe w/4" alum. MDNR cap. Set meas. nail with MDNR tag in the side of:
 8" W.Pine N46E 7.59' mrkd "1/64 BT"
 14" W.Pine S19E 19.34' do
 5" W.Pine N54W 22.38' do
 11" W.Pine N08W 26.29' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 05/07/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

