

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 48 . NR. 17 . . W

A l g e r . . . . . COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 25, 26, 35, 36 . . .

DESCRIPTION OF CORNER MONUMENT . . . 1" Pipe with 4" Brass Cap . . . . .

WITNESSES TO CORNER 8" Maple . . . . . (S 25 NBT) . . . . . N 88° E . . . 13 Links .

7" Maple . . . . . (S 35 NBT) . . . . . S 80° W . . . 21 Links .

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by double proportionated measurements, between section corners to south, west and north and 1/4 corner 1 1/2 miles to east. No evidence of original corner.

Corner was placed and witnessed August 10, 1960.

SURVEYORS SEAL

SIGNED Billy D. Buckler  
REGISTERED LAND SURVEYOR  
Billy D. Buckler

DATE 9/14/60