

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 48. NR. 12. W

Alger COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 23, 24, 25, 26

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 15" Y. Birch (S 24 NBT) N 50° E 44 Links

8" Soft Maple (S 26 NBT) S 16° W 33 Links

15" Hard Maple (S 23 NBT) N 70° W 69 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was replaced at LES post. Found down and rotted Maple S 25° E 11 Links with rotted out faces. Position fits with streams and corners east and west. Corner lies 25 Links south of road.

Corner was placed and witnessed August 9, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED

*Billy D. Buckler*  
REGISTERED LAND SURVEYOR  
Billy D. Buckler

DATE 9/14/60