

**JAN 18 2001**

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12-23-2000  
Donald W. Kinnunen  
Chairman

For corners in **SECTION** **LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

<u>Alger</u> (County)	Located In:	Corner Code #
	48N 14W	M.C. A09-B09
1. Public Land Survey	T ___ R ___	<u>#002</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**FILED** 05-203  
**TIME** 8:50 Am  
**DEC 20 2000**  
DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI  
**Register of Deeds Stamp & File Number**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Jamros, in a field survey on October 19, 2000  
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current  
manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and  
5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a  
Decree of a Court of Law; established, re-established, monumented, recovered, found  
as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**  
**MC A09-B09:** PLS Geo. E. Adair, DS, 1851. Corrected between Sections 19 and 30. Run by the  
needle. East 6.93 chains, Fir 6"; 8.97 chains. Intersect lake and set post at meander  
corner. W. Pine 12", N.81°W., 53 links. W. Pine 7", S.45°W., 12 links. \*\*\*\*\* No other  
subsequent restoration of record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
**MC A09-B09:** Found 1 1/4" iron pipe on the West shore of Grass Lake. From existing pipe located  
search areas for original BT's. At BT location bearing Northwest from iron pipe found  
remains of a stump and roots identified as W. Pine. At BT location bearing Southwest from  
iron pipe found a W. Pine stump with Easterly face weathered away. G.L.O. call of 8.97  
chains to section corner West on range line measured, 8.93 chains. Existing iron pipe as  
found is accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
**MC A09-B09:** Set 2 1/2" x 30" Berntsen aluminum monument no. A1NB30 with 3/4" aluminum cap  
stamped to identify corner position. New monument was set over existing 1 1/4" iron pipe.  
Established reference trees with BT signs, blazed, scribed and painted. Set PK nails for  
measure with aluminum I.D. washers in the following: Hemlock 12", N.59°W., 18.47 feet (MC  
BT); Balsam 7", N.64°W., 12.56 feet (MC BT); Balsam 6", S.25°W., 15.83 feet (MC BT);  
Balsam 3", S.05°E., 9.83 feet (blaze only). Survey marker sign on 6 foot steel post, S.80°W.,  
1.1 feet. All bearings are magnetic.

Signed by Robert L. Jamros Date Dec. 17, 2000  
Surveyor's Michigan License No. 25849

