

**SURVEY &
REMONUMENTATION**

FEB 19 1998

05-88

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 845 of
P.A. of 1990 On 12-10-97

Gerald W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____
(County)

Located In:

Corner Code #

		49	13	<u>A7</u>
1. Public Land Survey	T	<u>49N</u>	R <u>14W</u>	<u>M7</u>
	T	_____	R _____	_____
	T	_____	R _____	_____
2. Property Controlling in Section	S	_____	R _____	_____
	S	_____	R _____	_____
3. Miscellaneous Property in Section	S	_____	R _____	_____
	S	_____	R _____	_____

F.L.E.D
TIME 8:30 A.M.

DEC 17 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Jamros, in a field survey on August 05, 1997, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A7: PLS - John Burt, DS, 1841 * Set post corner of Sections 18 and 19 * Beech 16, S.53 E., 42 links * Hemlock 12, N.16 W., 17 links * Francis Colman, DS, 1851 * Fir 6, N.64 E., 44 links * Hemlock 16, S.37 W., 44 links **** George L. Depew, DS, 1917 * Set iron corner according to original Survey **** M.D.S.H., Survey and Construction Plans for M-77, 1958 * Corner position shown at intersection of roads East and West * 1 1/2 inch iron pin * Witnesses - Tele. Pole, N.37 W., 44.41 feet * Power Pole, S.60 E., 39.61 feet * Maple 5, S.36 W., 53.82 feet **** Gerald W. Carlson, RLS, 1978 * Found 1 inch solid iron in monument box, 1.5 feet West of centerline of M-77 * Witnesses - Maple Cluster 5, N.62 W., 50.26 feet * Beech 10, N.64 E., 64.18 feet * Power Pole, S.58 E., 38.16 feet * Anchor Pole, S.58 W., 49.77 feet * Recorded in Liber 1 on page 175, Alger County Corner Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A7: Found 1 inch iron bar in monument box, 1.5 feet West of centerline pavement of M-77 * Found 2 BT's and relationship of East and West side roads, as recorded in 1978 report by Gerald W. Carlson. * Corner position accepted locally and used as the true corner position. Measurements to adjacent corners check well. * Established new references * Monument box and corner position as found is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A7: Replaced 1 inch iron bar with a 5/8 inch by 18 inch Rebar w/8erntsen Alum. cap no. R8D 5325, stamped to identify corner position * Established references w/BT signs only * Set PK nails w/Alum. I.D. washers for measure in the following - Beech 3, N.61 E., 79.23 feet * Maple 11, S.52 E., 77.11 feet * Anchor Pole, S.62 W., 47.65 feet, scribed "BT" at base, no BT signs * Exist. BT, Maple 13, N.60 W., 50.31 feet * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12/12/1997

