

DEC 27 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12-8 1999

Donald W. Kinnunen
Chairman

For corners in SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-145

ALGER (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 13W T 49N R 14W T _____ R _____ T _____ R _____	A8 ✓ M8 _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED
TIME 1:30 p.m.

DEC 15 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Jamros, in a field survey on May 05, 1999, 19_____, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, _____ recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A8: PLS * John Burt, DS, for William A. Burt, DS, 1841. * Set quarter section post * Tamarack 8', S.61 W., 117 links (only 1 reference shown in notes of 2 townships). **** George L. Depew, CS, 1917. * Set iron corner on true line between section corners, overall distance 5278 feet. * No references. **** Michigan State Highway Department, 1958, Highway Improvement Plans of M-77. * At highway station 689+35 feet, approximate East-West quarter line shown, no corner position shown. **** No other subsequent restoration on record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A8: No corner monument found. * Established corner position at mid-point and on line between section corners North and South. * GLO stream calls of 1 chain South, stream, 4 links, C-E AND 1 chain North, stream, 2 links, C-E, have been relocated into 1 stream crossing by culvert, 39 feet South of corner position. Area around highway and corner position is an open marsh and original BT has been lost. * Corner position as established is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A8: Set 5/8"x18" rebar with Berntsen 3 1/4" aluminum cap No. RBD 5325, stamped to identify corner position. * Established the following references: Power pole, S.27 E., 84.05 feet to a PK nail with aluminum I.D. washer. * West end of 36" C.M.P. culvert, S.27 W., 40.83 feet to a PK nail with aluminum I.D. washer. * East end of 36" C.M.P. culvert, S.47 E., 56.62 feet to a PK nail with aluminum I.D. washer. * Centerline of asphalt pavement on highway N-77, East, 15.6 feet. * No survey marker sign set along highway. * All bearings are magnetic.

Signed by *Robert L. Jamros*
Surveyor's Michigan License No. 25849

Date Dec 15 1999

