

DEC 8 7 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12-8-1999

Donald W. Kinnunen
Chairman

For corners in SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

ALGER <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 49N R 13W T <u>41N</u> R <u>14W</u> T _____ R _____ T _____ R _____	A9 ✓ <u>M9</u> _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

05-146

FILED
TIME 1:30 p.m.

DEC 15 1999
DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI
Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on May 05, 1999, 19_____, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, _____ recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	10	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A9: PLS * John Burt, DS, for William A. Burt, 1841. * Set post corner of Sections 19 & 30. * Birch 6", S.46 W., 27 links. * Cedar 14", N.62 E., 26 links. **** George L. Depew, CS, 1917. * Set iron corner according to original survey notes. * No references. **** Michigan State Highway Department, 1958, Highway Improvement Plans for M-77. * Wood post. * 4" Birch, S.50 W., 16.60 feet. * Birch, S.85 W., 23.15 feet. * 6" Birch, N.77 W., 21.20 feet. **** No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A9: Established corner position using reference measurements from M.D.S.H. Improvement Plans of Highway M-77. Recovered curve P.I. of highway at Station 660+40.66 feet from references on highway plans. Established corner position as shown 312.53 feet North along tangent line and 26.72 feet West of tangent line of highway curve. Position falls on line between 2 concrete right of way markers, East and West, and 58.1 feet from centerline of highway, record is 57.96 feet. Highway plan references and wood post have been destroyed and lost. Distance by highway station to section corner to the North is 5294.25 feet, measured is 5284.90 feet. Highway station of a 36" C.M.P. culvert is 662+50 feet. Distance between culvert and section corner by station is 37 feet, found and measured as 35 feet. Corner position as established is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A9: Set 2 1/2"x30" Berntsen aluminum monument No. A1NB30 with 3 1/4" aluminum cap stamped to identify corner position. * Established the following references: Chiseled 'X' in the centerline of the East concrete headwall of the existing culvert under Highway M-77, S.45 W., 53.63 feet. * Power pole, N.70 E., 60.00 feet with PK nail with aluminum I.D. washer for measure and scribed 'BT'. * W. Birch 5", S.23 E., 7.00 feet with BT signs, blazed and scribed 'BT'. * Set PK nails with aluminum I.D. washer for measure. * Survey marker sign on 6 foot steel post, N.46 E., 1.5 feet. * No other references available. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date Dec. 13, 1999

