

Approved by Alger County
Land Survey Monumentation
Peer Group Under Act 345 of
P.A. of 1990 On 3-24-1997

Gerald Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

5-29

For corners in ALGER (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>13W</u>	<u>85</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED
TIME 2:00 p.m.

MAR 31 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on October 04, 1996, 19_____
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B5: PLS - Francis Colman, DS, 1851, Set quarter Section post on West border of Hemlock land, C N&S * Hemlock 16, N.43 E., 22 links * W. Birch 8, S.24 W., 9 links ***** Mel Davis, RLS, 1971. * Set 1" X 18' iron in graveled road. Set corner on a direct line with and at a proportionate distance between the section corners to the East and West. * Witness, Axel Bar, North, 41.75 feet. * Centerline Elec. Pole, N.54 E., 51.80 feet. * Well point at fence corner, S.22 W., 48.55 feet. * Recorded in L.1, P.5, Alger County records. ***** Gerald W. Carlson; RLS, 1978. * Found bent iron pipe, replaced w/ 5/8" X 18" Iron w/ RLS cap. Two feet South of centerline of East-West road and 80 feet East of centerline of drive on South side of road. * Witness, Power Pole, N.56 E., 51.92 feet. * Axle bar, 1.5 feet high, N.07 E., 41.70 feet. * Well point at fence corner, S.22 W., 48.55 feet. * 4" W. Birch, N.26 W., 85.79 feet. * Recorded in L.1, P.175, Alger County Records. *****


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B5: Found 5/8" iron w/ RLS cap. Verified corner position by measurements from the reference objects on corner reports of 1971 and 1978. Replaced existing cap with 3 1/4" Aluminum Cap stamped to identify corner position. Renewed existing references and added additional references. Monument at existing corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B5: Set 3 1/4" Aluminum Cap stamped to identify corner position. * Renewed existing reference objects w/ BT signs and paint. * Established additional reference trees w/ BT signs, blazed, scribed and painted. * Set PK nails for measure w/ Alum. I.D. washers in the following reference trees. * Balsam 7", S.29 E., 54.07 feet, "1/4S BT". * Balsam 10", S.60 W., 82.68 feet, "1/4S BT". * Exist. BT, W. Birch 12", N.31 W., 86.07 feet, Existing blazes. * Exist. BT, Axle Shaft, N.08 E., 41.62 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849



Date 25 March, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983