

# SURVEY & REMONUMENTATION

FEB 19 1998

05-87

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12-10-97

Gerald W. Carlson  
Chairman

## LAND CORNER RESTORATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in \_\_\_\_\_

(County)

Located In: \_\_\_\_\_

Corner Code # \_\_\_\_\_

1. Public Land Survey	T	<u>49</u>	R	<u>13</u>	<u>B7</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

FILED  
TIME 8:30

DEC 17 1997

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert L. Jamros, in a field survey on December 01, 1997, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7	•												
8	19	18	17	16	15	14	13	12	11	10	9	8	7
9													
10	30	29	28	27	26	25							
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

B7: PLS - Francis Colman, DS, 1951 \* Set quarter section post \* Sugar 14, N.55 W., 28 links \* Beech 8, S.17 E., 16 links \*\*\*\* George L. Depew, County Surveyor, 1917 \* Set iron corner from 1 BT \* No references given \*\*\*\* M.D.S.H., Survey and Construction Plans for M-77, 1958 \* Corner position shown 2523.86 feet East of centerline of M-77 \* 1 inch iron pipe \* Witnesses - Beech 10, due North 27.50 feet \* Maple 7, N.42 W., 20.10 feet \* Beech 7, S.15 E., 16.50 feet \*\*\*\* Gerald W. Carlson, RLS, 1978 \* Set 5/8 inch by 19 inch iron w/RLS cap from M.D.S.H. & T. witnesses on file \* 1 inch iron, 1.5 feet high, 5.80 feet South on bank of road \* Witnesses - Yellow Birch 4, N.03 W., 32.26 feet \* Maple 8, N.41 W., 27.09 feet \* Beech 12, S.02 W., 15.25 feet \* Beech, S.29 E., 10.60 feet \* Recorded in Liber 1, Page 175, Alger County Corner Records \*\*\*\* No other subsequent restoration on record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

B7: Found 5/8 inch Rebar w/cap by field survey \* Corner position as witnessed in 1978 report checks well with remaining BT's \* Measurement to centerline of State Highway M-77 is 2527 feet \* Exist. \* Paint lines running North and South from corner position with developed occupation to the West. \* Exist. corner position is accepted and used as true corner position by the surrounding area \* Installed new monument at exist. corner position, renewed exist. BT's and established additional reference trees \* Corner position as found is accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

B7: Installed over the exist. 5/8 inch Rebar a Berntsen Alum. monument cap no. A1N830, stamped to identify corner position. Renewed exist. BT's and established new reference trees w/BT signs, blazed and scribed \* Set PK nails w/Alun. I.O. washers for measure in the following \* Exist. BT, Maple 7, N.45 W., 27.1 feet \* BT \* Maple 9, N.51 E., 55.3 feet \* BT \* Yellow Birch 8, S.25 E., 10.53 feet, \* BT \* Exist. BT, Beech 8, S.25 E., 10.53 feet, \* BT \* Survey marker sign on 6 foot steel post, South, 1.0 feet \* All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date 12/1/97

