

# SURVEY & REMONUMENTATION

JUL 30 1996

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 5/8 1996

## COMMISSION LAND CORNER RECORDATION CERTIFICATE

4-372

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alger  
(County)

Located In:

Corner Code #

FILED  
TIME 3:00 p.m.

- |   |              |               |          |
|---|--------------|---------------|----------|
| 1. Public Land Survey                   | T <u>49N</u> | R <u>R13W</u> | 89 _____ |
|   | T _____      | R _____       | _____    |
|   | T _____      | R _____       | _____    |
|   | T _____      | R _____       | _____    |
| 2. Property Controlling<br>in Section   | S _____      | T _____       | R _____  |
|   | S _____      | T _____       | R _____  |
| 3. Miscellaneous<br>Property in Section | S _____      | T _____       | R _____  |
|   | S _____      | T _____       | R _____  |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

JUN 27 1996

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on March 05, 1996, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

B9: PLS-Francis Coleman, DS, 1851, Set qr. section post - Sugar 24", N.31 E., 39 links, Sugar 12", S.44 W., 30 links.\*\*\*\* George L. Depew, County Surveyor, 1916, Set iron corner from government field notes. No references given. Record of surveys book, page 264, Alger County Records.\*\*\*\* CCI Forestry Division, Land and Timber Examination Report, T.J. McLaren, 1957, indicates a Sugar BT at corner position. No references given. No other subsequent restoration.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

B9: Found Alger County Standard Monument with brass cap dated March 1916. Also found a splintered large Maple stub eight feet high at GLO BT location, N.31 E., 39 links. Area on tree that contained the blazing and scribing is splintered and decayed. Old blaze lines E, W, and S. from the monument position. Existing brass capped monument measures well with large Maple stub at BT location and is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

B9: Stamped P.A. 345 in brass cap of cast steel monument. Established reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ Alum. I.D. washers in the following reference trees. Maple 20", S.66 E., 27.65 feet, " 1/4s BT ", Maple 8", N.24 E., 30.18 feet, " 1/4s BT ", Beech 10", N.60 W., 33.15 feet, " 1/4s BT ", Beech 8", S.31 W., 44.90 feet, " 1/4s BT ". Survey marker sign on six foot steel post, N.60 E., 0.9 feet. All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date 12 June 1996

