

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 5-18 1994

Robert L. Jamros
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-222

For corners in

Alger

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 49N R 13W C4
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

**SURVEY &
REMONUMENTATION**

MAY 10 1995

COMMISSION

Recorded May 26, 1994
at 8:00 o'clock A. M., and
Recorded in Liber 4 of Corner Rec
on Page 222

Donald W. Himmelman

Alger County Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Jamros, in a field survey on August 28, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C4: P.L.S. - Francis Coleman, DS, 1851. Set Gr. Sec. post - W. Birch 18, N.16 E, 16 links, Fir 10, S.78 W., 28 links. James Roundtree, County Surveyor, 1908, Iron driven according to field notes and barren trees. Alger County Rd. Comm., iron on true line and equal dist., 1917. Mel Davis, RLS, 1971, found 1/2' rebar set by persons unknown, A.C.Rec.No.3. Robert L. Jamros, RLS, 1978, set 1/2' rebar on line at proportional distance btwn. adjacent corners. A.C.Rec.No.158

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C4: At tee intersection of roads North, South and West located a 1/2" x 18" rebar with top half badly bent and bottom half still vertical and marking corner position. Accepted the rebar as a careful and faithful perpetuation of the position of the original corner. Installed monument in ground hole marking corner position and established new references. Top of new monument was placed 12 inches below surface of gravel road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C4: Installed 5/8" x 18" rebar w/ 3
1/4" Alum. cap in place of 1/2" rebar,
stamped to I.D. corner position. Est.
reference trees w/BT signs, blazed,
scribed and painted. Set PK nails for
measuring w/brass I.D. washers in the
following reference trees. Exist BT -
Y. Birch 20", S.40 E., 69.41 ft., "BT".
W. Birch 12", N.15 W., 90.20 ft., "BT".
Aspen 10", N.28 E., 91.70 ft., "BT".
Tele pedistal, S.41 W., 42.18 ft.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 2 May, 1994