

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12-12-1995

Gerald W. Carlson  
Chairman

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 23 1996

COMMISSION

For corners in

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>13W</u>	<u>C7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4-320

REC'D and FILED

DEC 20 1995

2:45 p.m.

DONALD W. KINNUNEN, County Clerk  
ALGER COUNTY, MI  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7		●											
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Jamros, in a field survey on June 21, 1995, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C7: PLS-Francis Coleman, DS, 1851, Set post corner of sections 17,18,19 & 20 - Cedar 20", N.70 W., 47 links, Cedar 14", S.27 E., 15 links. Walter W. Gleason, County Surveyor, 1914, Set iron corner at section line intersections. No references given. Survey book of records, page 180. Alger County Records. Alger County Road Commission Notes, George Depew, County Surveyor, 1916, iron corner shown. References: Hemlock 9", N.37 W., 50 feet, Cedar 12", S.30 E., 50.50 feet. CCI Forestry Division, Land and Timber Examination Report. T.J. McLaren, 1952, indicates a 5" cedar post at corner position. No references given. Gerald W. Carlson, RLS, 1978, Set 5/8" rebar at intersection of north and east roads and at recorded bearing and distance from cedar witness tree. References: Cedar 20", S.35 E., 51.08', Spruce 15", S.13 E., 40.47', W. Birch S.36 E., 42.57', W. Birch 10", N.47 E., 39.62'. Filing No. 175 Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C7: Found 5/8" rebar with identification cap Number 24589 at the centerline of roads to North and East. Verified witnesses of the 1978 report to be in agreement with corner position. A search was made for GLO bearing tree positions, evidence has been lost. Corner position is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C7: Placed Berntsen Cap no. R8D5325 on existing 5/8" rebar, stamped to identify corner position. Renewed existing reference trees w/ BT signs and paint. Established additional reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ Alum. I.D. washers in the following reference trees. Ex. Y. Birch 16", N.40 E., 68.82 feet, " face Blzd.", Ex. W. Birch 8", S.18 W., 25.27 feet, " face Blzd.", Maple 4", N.40 W., 32.46 feet, " S18 BT ", Y. Birch 6", S.52 E., 54.11 feet, " S20 BT ", All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

