

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 5-18 1994

Robert L. Jamros
Chairman

For corners in
Alger

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-220

(County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 13W	D3
	T _____ R _____	SURVEY &
	T _____ R _____	REMONUMENTATION
	T _____ R _____	MAY 10 1995
	T _____ R _____	COMMISSION
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Recorded May 26, 1994
at 8:00 o'clock A. M., and
Recorded in Liber 4 of Corner Rec.
on Page 220

Robert L. Jamros
Alger County Register of Deeds

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on August 28, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D3: P.L.S. - Francis Coleman, DS, 1851. Set Or. Sec. post - Sugar 14, N.36 E., 18 links. Sugar 8, S.08 W., 32 links. James Roundtree, County Surveyor, 1908, iron driven according to field notes and barren trees. Plat Records, Alger County, corner shown as part of Grand Marais Heights #1 Subdivision, L.1, P.56. Gerald W. Carlson, RLS, 1984 found 5/8 iron bar in centerline of E-W road at 2 track road South, A.C.Rec.No.4-16. Robert L. Jamros, RLS, 1986, found 3/4" iron bar 1 foot north of centerline of gravel road on centerline of 2 track south, A.C.Rec.No. 3-357.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D3: Beginning at Section corner 5, 6, 7, and 8, T.49 N., R.13 W., clocked by odometer to East one half mile. At corner location found evidence of recent reference trees. Evidence of original BT's was destroyed during construction of County Road. With the aid of recent reference trees located erroded iron bar, approx. 3/4" in diameter, one foot below surface of gravel. Installed alum. cap on existing iron bar and renewed existing reference points, and is accepted as a careful and faithful perpetuation of the position of the original corner. Corner lies adjacent to subdivision Plat of Grand Marais Heights No. 1 and in centerline of inter of county gravel road and dirt drive to South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

iron, stamped to I.D. corner position. Est. reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. Exist - Maple 9", S.66 W., 54.78 ft., "BT" Exist - W. Birch 18", N.67 W., 69.10 ft., "BT". Exist - Power pole, N.18 E., 33.13 ft., "BT". Exist - Aspen 9", S.34 E., 41.09 ft., "BT".

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3				●									
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by

Robert L. Jamros

Date

2 May 1994

Surveyor's Michigan License No.

25249