

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 5-18 1994

Robert L. Jamros
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-218

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>13W</u>	E2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Recorded May 26, 1994
at 8:00 o'clock A. M., and
Recorded in Liber 4 of Corner Rec
on Page 218

David W. Kinnaman
Alger County Register of Deeds

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on July 24, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

E2: P.L.S. - Francis Coleman, OS, 1851. Set Qr. Sec. post - Henlock 25, N.41. W., 17 links, Cedar 16, S.40 E., 19 links. James Rountree, County Surveyor, 1908, iron driven according to field notes and barren trees. Alger County R.C. Corner shown on Alignment survey drawing, 1936. Billy D. Buckler, RLS, 1973, found concrete plat monument, A.C.Rec.No.31. Robert L. Jamros, RLS, 1981, found iron bar encased in 4" x 4" concrete, A.C.Rec.No.405. Gerald W. Carlson, RLS, 1984 found concrete monument at intersection of roads, A.C.Rec.No.4-16.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E2: Located corner position at the centerline of intersection of County Road H-58 East (Asphalt) and East Bay Road. Found 1/2 inch rebar w/plastic cap no. 25849 encased in concrete 4 inches square below asphalt road surface. Installed aluminum cap on 1/2 inch rebar, renewed existing reference points and also established new reference points. Corner position is well established and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E2: Installed 3 1/4" Alum. cap on exist 1/2" rebar in 4" x 4" conc. base and grouted around cap with cement. Stamped to I.D. corner position. Est. reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. Exist - Maple 24", N.33 E., 61.0 ft., "BT". Power Pole, N.42 W., 45.43 ft., "BT". Exist - Twin Maple, 8"-12", S.59 W., 88.79 ft., "1/4S-BT". Twin W. birch, 6"-10", S.25

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 2 May 1994