

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 5-18-94

Robert L. Jamros
Chairman
For corners in
Alger
(County)

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-216

	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>13W</u>	E4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded May 26, 1994
at 8:00 o'clock A. M., and
Recorded in Liber 4 of Corner Rec.
on Page 216
Du. W. Kimmunen
Alger County Register of Deeds

Register of Deeds Stamp & File Number

COMMISSION

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Jamros, in a field survey on July 24, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E4: P.L.S. - Francis Coleman, DS, 1851. Set Qr. Sec. post - Sugar 24, N.37 W., 17 links. Fir 6, S.44 E., 5 links. Robert L. Jamros, RLS, 1986, corner position determined by field survey. Found 1 1/2" pipe at position, author unknown. Corner lies 1 1/2 feet West of centerline of N-S woods road and on centerline of diw two track West. Existing corner position proportionately sets well with East line of Section. A.C.Rec.No.3-356.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E4: By odometer clocked South along dirt road from Section corner 4,5,8 & 9 to corner location. With the aid of existing reference trees found 1 1/2 inch pipe, very old, thin and porous 8 inches below surface of dirt road. South of this 1/4 Section corner the G.L.O. notes have a terrain call for a stream 10 links, C NE at 6.25 chains. Measuring South from the 1 1/2 inch pipe to a dry stream bed, approx 15 links C NE, we marked a distance of 6.36 chains. The original BT's fall in graded area of road and all evidence has been lost. Installed monument over existing iron and renewed existing reference points and is accepted as a careful and faithful perpetuation of the position of the original corner. Corner lies in the centerline of N-S dirt road at the centerline of a dirt road west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E4: Installed 2 1/4 Alum. Mon. w/3 1/4 Alum. cap over exist. 1 1/2" pipe. Stamped to I.D. corner position. Est. reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. Exist - Maple 12", S.61 E., 27.21 ft., "1/4S-BT". Exist - Maple 5", S.49 W., 43.49 ft., "1/4S-BT". Exist - Maple 10", N.25 W., 32.47 ft., "1/4S-BT". Exist - Maple 11", N.34 E., 50.27 ft.,

Signed by Robert L. Jamros Date 2 May 1994
Surveyor's Michigan License No. 25849