

SURVEY & REMONUMENTATION

FEB 23 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-97

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On Feb 16 1998
Robert L. Jamros
Chairman

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>13W</u>	<u>E 5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED
TIME 10:00 A.M.

JAN 8 1999
DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on June 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5		4	3	2	1					
3												
4	7	8		9	10	11	12					
5				●								
6	18	17		16	15	14	13					
7												
8	19	20		21	22	23	24					
9												
10	30	29		28	27	26	25					
11												
12	31	32		33	34	35	36					
13												

A. Description of original monument and accessories and/or subsequent restoration:

E5: P.L.S. - Francis Colman, DS, 1851. Set post corner of Secs. 8, 9, 16 & 17. Sugar 16, N.70°W., 3 links. Beech 12, S.27°E., 13 links. ***** C.C.I. Co., Land Corner Record, 1968, T.J. McLaren, Set post at corner position, 1949, from original BT. Sugar 16", N.70°W., 3 links (stump very rotten, 1949). Witnesses to corner, * Beech 15, S.67E., 18.9 feet; * Sugar 11, S.20°W., 21.6 feet. ***** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E5: Located corner position by standard field survey and double proportionate measurement. Post set in 1949 gone and area heavily logged in recent past. Found stump of 1949 Beech BT in SE, cut for timber. In SW position found Maple BT of 1949 standing live. Established corner position from Beech stump and standing Maple BT and established reference trees. Corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E5: Set Berntsen aluminum monument no. AINB30 with 3 1/4" aluminum cap, stamped to identify corner position. Established 3 new reference trees with BT signs, blazed, scribed and painted. Renewed 1 existing reference tree with BT signs and paint. Set PK nails for measure with aluminum I.D. washers in the following reference trees. * Existing - Maple 16", S.27°W., 21.78 feet; * Beech 16", N.48°W., 25.76 feet, "S8 BT"; * Maple 16", N.47°E., 26.18 feet, "S9 BT"; * Maple 20", S.62°E., 34.10 feet, "S16 BT"; * Survey marker sign on 6 foot steel post, S.63°W., 1.0 feet. All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date December 16, 1998

