

**SURVEY &
REMONUMENTATION**

FEB 23 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12/16 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-99

McLaurin RLS
Chairman

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T49N R13W	F 2
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

FILED
TIME 10:00 AM.

JAN 8 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5		4		3		2		1		
3												
4	7	8		9		10		11		12		
5												
6	18	17		16		15		14		13		
7												
8	19	20		21		22		23		24		
9												
10	30	29		28		27		26		25		
11												
12	31	32		33		34		35		36		
13												

I, Robert L. Jamros, in a field survey on July 14, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F2: This corner position not established as part of the Public Land Surveys. Corner position established by Edwin Swan, RLS No. 2214, 1947, no witnesses given. ***** Billy D. Buckler, RLS, 1973. Found cedar post set by Edwin Swan. * Set 1" pipe with 4" aluminum cap. * Cedar post and monument are on North bank of Sucker River. No new witnesses available. Liber 1, Page 39, Alger County Corner Records. ***** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F2: Located corner position by standard field survey and intersection of North-South and East-West 1/4 lines in Section 4. Found squared 6" cedar post and 1" G.I.P. with aluminum cap. Existing monuments lies 33.5 feet East and 14.7 feet South of the calculated intersection of the East-West quarter lines. No reference objects available. Established 2 witness corners. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F2: Existing 1" G.I.P. with 4" brass cap. Corner positions lies on North bank of the Sucker River, 50 feet wide. No witness objects available. Established 2 witness corners consisting of 1/2" by 18" rebars with I.D. caps in the following positions, N.63° 33'W., 6.03 feet, and N.20° 51'E., 5.96 feet. Set carsonite survey marker posts, North 1.0 feet, from each witness corner. Bearings are true bearings.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date December 16, 1998

