

# SURVEY & REMONUMENTATION

FEB 19 1998

## SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

05-86

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12-10-1997

Healdie Wilson  
Chairman

For corners in \_\_\_\_\_

(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>49</u>	R	<u>13</u>	F3
	T		R		F3
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous	S		T		
Property in Section	S		T		

FILED  
TIME 8:30 Am.

DEC 17 1997

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert L. Jamros, in a field survey on August 04, 1997, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

F3: PLS - Francis Colman, OS, 1851 \* Set quarter section post \* Hemlock 16, N.48 E., 47 links \* White Birch 6, S.55 W., 20 links \*\*\*\*  
Billy D. Buckler, RLS, 1973 \* Found wood post with remains of Hemlock stump in proper position \* Believe post was set by Edwin Swan, RLS, 1950 \* Witnesses - Cedar 5, S.64 E., 24.6 feet \* Cedar 5, N.57 E., 36.3 feet \*\*\*\* Recorded in Liber 1, Page 31, Alger County Corner Records.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

F3: Found both BT's of the 1973 recorded report. monument and wood post gone \* GLO notes recorded a winding stream, 2 chains North of corner position, found to be at this time approximately 60 feet. Stream lies in wide bottom plateau and is subject to relocation with seasonal changes \* Found large decayed Hemlock stump in the GLO position of N.48 E., 47 links, GLO BT White Birch 6, S.55 W., 20 links. is beyond recovery \* Established corner position from 1973 recorded BT's and remains of Hemlock stump \* Renewed exist. BT's and established additional reference trees \* Corner position accepted and used locally by adjacent properties \* Corner position has been accepted and used for property surveys \* Corner position from exist. BT's is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

F3: Set Berntsen Alum. monument no. A1NB30, stamped to identify corner position \* Renewed exist. BT's w/signs and paint \* Established additional reference trees w/BT signs, blazed, scribed and painted \* Set PK nails w/Alum. I.G. washers in the following - Exist. BT, Cedar 8, S.57 E., 24.82 feet, dbl. blzd. \* Exist. BT, Cedar 9, N.62 E., 36.26 feet, dbl. blzd. \* Cedar 6, N.72 E., 0.84 feet, "1/4S BT" \* Balsam 10, S.47 W., 20.12 feet, "1/4S BT" \* Survey marker sign on 6 foot steel post, S.80 E., 1.25 feet \* All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date 12/10/1997

