

FEB 23 1999

SECTION

Approved by Alger County Land Survey Remonumentation Peer Group Under Act 345 of P.A. of 1990 On 12/16/1998
M. Davis RLS
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-100

For corners in

_____ Alger _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T49N R13W	F 5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED
TIME 10:00 AM.

JAN 8 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5						●							
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Robert L. Jamros, in a field survey on October 20, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F5: P.L.S. - Francis Colman, DS, 1851. Set quarter section post. Beech 10, N.75°W., 42 links. Beech 9, S.22°E., 47 links. ***** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F5: Located corner position by standard field survey and single proportionate measurement. Found evidence of old blaze lines in all cardinal directions and a 24" Beech blazed on 4 sides, 20 feet East of corner position. GLO evidence destroyed. Set monument at corner position and established reference trees. Monument as set is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F5: Set Berntsen aluminum monument no. AINB30, with 3 1/4" aluminum cap, stamped to identify corner position. Established the following reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure with aluminum I.D. washers in the following reference trees. * Maple 28", S.40°W., 1.25 feet, *1/4S BT"; * Maple 14", N.34°W., 10.80 feet, *1/4S BT"; * Maple 20", N.59°E., 13.23 feet, *1/4S BT"; * Beech 6", S.26°E., 15.02 feet, *1/4S BT"; * Survey marker sign on 6 foot steel post, N.72°W., 1.2 feet. All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date December 16, 1998

