

Robert L. Jamros  
Chairman

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

4-214

For corners in  
Alger

	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>13W</u>	<u>61</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded May 26, 1994  
at 8:00 o'clock A. M., and  
Recorded in Liber 4 of Corner Rec.  
on Page 214

Robert W. Kimmman  
Alger County Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert L. Jamros, in a field survey on August 08, 1993, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G1: P.L.S. John Burt, DS, for William A. Burt, DS, 1841. Set post corner of Sections 3 and 4 T.49 N., R.13 W., Y.Pine 4, N.48 E., 69, W. Birch 6, N.05 W., 66. Subsequent restoration made by authors unknown. Evident by iron pipe and 4" squared post found at corner. C.C.I. Forestry - Btwn. 1947 and 1968, noted on Land and Timber Examination Report a 6" sq. post at corner position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G1: Beginning at 1/4 Section corner Section 33, T.50N., R.13 W., and Section 4, T.49N., R.13W. East on a corrected compass line from above 1/4 Section corner measured and marked in at existing corner 2638.0 feet more or less. Found 4" squared top post and one inch G.I.P. lying 9 feet Sly of an existing sand track road. Investigated the original BT position of N.5 W., 66 links and found no evidence of W. Birch, area has been replanted. In the original BT position of N.48 E., 69 links found charred remains of a Y. Pine stump. Installed monument over existing pipe and established new reference tree, and is accepted as a careful and faithful perpetuation of the position of the original corner. Inter. of track roads, N.39 W., 23.0 feet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G1: Installed 2 1/4" Alum. monument w/3 1/4" Alum. cap over existing 1" G.I.P., stamped to I.D. corner position. Est. reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. J. Pine 12", N.40 E., 45.11 ft., "S33-BT". R. Pine 10", S.20 E., 27.70 ft., "S3-BT". R. Pine 13", S.59 W., 24.24 ft., "S4-BT". R. Pine 11", N.32 W., 50.66 ft., "S34-BT". Sur. Marker sign, South, 1.0

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date 2 May, 1994