

SURVEY & REMONUMENTATION

FEB 19 1998

Approved by _____
 Land Survey Remonumentation
 Peer Group Under Act 343 of
 P.A. of 1990 On 12-10-1997

05-85

SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____ Located In: _____ Corner Code # _____
County

		49	13	G2	
1. Public Land Survey	T	<u>49</u>	R <u>13</u>	<u>G2</u>	_____
	T	_____	R _____	_____	_____
	T	_____	R _____	_____	_____
	T	_____	R _____	_____	_____
2. Property Controlling in Section	S	_____	T _____	_____	_____
	S	_____	T _____	_____	_____
3. Miscellaneous Property in Section	S	_____	T _____	_____	_____
	S	_____	T _____	_____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

FILED
 TIME 8:30 A.M.
 DEC 17 1997
 DONALD W. KINNUNEN
 REGISTER OF DEEDS
 BER COUNTY, MI
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1	●	1	2	3	4	5	6
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. James, in a field survey on December 04, 1997, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G2: PLS - Francis Tolman, DS, 1951, Set quarter section post - White Birch 4, N.35 W., 36 links * Yellow Pine 4, S.69 E., 25 links.**** T.J. McLaren, 1949, C.C.I. Co., Forestry Division * Indicates a 6 inch squared post on Land and Timber Report, unrecorded **** Thomas P. O'Brien, RLS, 1992 * Found 1/2 inch pipe at a position South of GLO distance from the Northeast corner of section, no GLO evidence exists * Unrecorded report **** No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G2: Found 1 iron iron pipe by field survey, South of proportioned corner position * Existing iron pipe measures well to East line of recorded Plat of AGATE POINTE No. 2, being part of Section 4, Township 49 North, Range 13 West and Section 33, Township 50 North, Range 13 West * A recorded survey of the Southwest quarter of Section 4 measures very well to the existing iron pipe position. L.1,P.31, Alger County corner records. Surveyed by Billy D. Buckler, RLS, 1973 * The collateral evidence supports the existing pipe position as being accepted and used * Existing corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G2: Installed over exist. pipe a Berntsen Alum. monument cap no. A1N830, stamped to identify corner position * Established reference trees with BT signs, blazed and scribed * Set PK nails w/Alum. I.D. washers for measure in the following - Red Pine 6, N.47 W., 10.15 feet, "1/4S BT" * Red Pine 4, N.62 E., 12.39 feet, "BT" * Jack Pine 10, S.40 W., 8.92 feet, "1/4S BT" * Red Pine 16, S.41 W., 37.20 feet, "1/4S BT" * Survey marker sign on 6 foot steel post, South, 1.10 feet * All bearings are magnetic.

Signed by Robert L. James
 Surveyor's Michigan License No. 25849

Date 12/10/1997

