

**SURVEY &
REMONUMENTATION**

FEB 19 1998

SECTION

05-84

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 845 of
P.A. of 1990 On 12-10-97

Donald W. Kinnunen
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____

(County)

Located In:

Corner Code #

FILED
TIME 8:30 A.M.

1. Public Land Survey	T	<u>49</u>	R	<u>13</u>	G4
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

DEC 17 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. James, in a field survey on August 05, 1997, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G4: PLS - Francis Colman, OS, 1851 * Set quarter section post * Sugar 10, N.42 E., 50 links * Hemlock 14, S.21 W., 18 links ***** No other subsequent restoration on record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G4: Located corner position by field survey * Search in GLO BT position of N.42 E., 50 links fell on mound, but no evidence was found * GLO position of S.21 W., 18 links, falls in middle of East-West track road * GLO call for foot of bank 8 chains (528 feet) South was measured at 560 feet * East 4 feet stands a Maple 6, with blazes and paint on all 4 sides with blaze line running North, East and West * Corner position was established on true line at the mid point between section corners North and South * Corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G4: Set Berntsen Alum. monument no. A1N830, stamped to identify corner position * Established reference trees w/BT signs, blazed, scribed and painted * Set PK nails w/Alum. I.D. washers for measure in the following - Beech 8, N.46 W., 20.95 feet, '1/4S BT' * Beech 6, S.73 W., 16.00 feet, '1/4S BT' * Beech 5, S.71 E., 12.75 feet, '1/4S BT' * Maple 6, N.70 E., 8.75 feet, '1/4S BT' * Survey marker sign on 6 foot steel post, N.29 E., 1.2 feet * All bearings are magnetic.

Signed by Robert L. James
Surveyor's Michigan License No. 25849

Date 12/17/97

