

Approved by Alger County
 Land Survey Remonumentation
 Peer Group Under Act 345 of
 P.A. of 1990 On 5-18 1994

Robert L. James
 Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

4-213

For corners in
Alger
 (County)

Located In: Corner Code #

- | | | |
|------------------------------------|---------------------------|-----------|
| 1. Public Land Survey | T <u>49N</u> R <u>13W</u> | <u>65</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Recorded May 26, 1994
 at 8:00 o'clock A. M., and
 Recorded in Liber 4 of Corner Rec.
 on Page 213

Robert L. James
 Alger County Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert L. James, in a field survey on July 24, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

65: P.L.S. - Francis Coleman, DS, 1851. Set post corner of 9, 10, 15, & 16 - W. Birch 18, N.40 E., 37 links. Hemlock 18, S.42 W., 8 links. C.C.I. Forestry, btwn. 1947 and 1968. Noted on Land and Timber Examination Report. 22' Birch BT, L.E.S., post. C.C.I. Forestry, G. Mootie, 1964 Y. Birch BT here 1957, post set from bearing.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

65: Corner position as indicated on U.S.G.S. Quad map fell in or by a sand road. Clocked by odometer from M-58 East, South along sand road to Section line crossing and marked location. Found original Y. Birch stub (dead) with blazes and original scribing still visible. Original G.L.O. notes have a W. Birch as a BT and it is obvious that there is a transcribing error present. Established corner position from original Y. Birch BT, corner falls in the exist. sand road. Original Hemlock BT falls in road also and no evidence remains. Installed monument at corner position and established new reference trees, and is accepted as a careful and faithful perpetuation of the position of the original corner. Corner lies on centerline of N-S sand road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

65: Installed 2 1/4" Aluminum monument
 w 3 1/4" Aluminum cap stamped to I.D.
 corner position, 10 inches below surface
 of sand road. Est. reference trees w/BT
 signs, blazed, scribed and painted. Set
 PK nails for measuring w/brass I.D.
 washers in the following reference
 trees. Maple 14", N.71 E., 40.06 ft.,
 "S10-BT". Maple 10", N.42 W., 36.32
 ft., "S9-BT". Maple 9", S.60 W., 42.17
 ft., "S16-BT". Maple 10", S.36 E.,
 50.65 ft., "S15-BT". Sur. Marker Sign,

Signed by Robert L. James Date 2 May, 1994
 Surveyor's Michigan License No. 25489

