

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12-12, 1995

Donald W. Carlson
Chairman
For corners in
Alger

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
RECORDATION

JAN 23 1996

cb/mml/3/15

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>13W</u>	<u>69</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REC'D and FILED

DEC 20 1995

2:45 p.m.

DONALD W. KINNUNEN, County Clerk
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Jamros, in a field survey on June 21, 1995, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9							●						
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G9: PLS-Francis Coleman, DS, 1851, Set post corner of sections 21, 22, 27 & 28 - Spruce 8", N. 28 E., 6 links, Y. Birch 30", S. 64 W., 39 links. CCI Forestry Division, Land and Timber Examination Report, Henry Carpenter, 1946, on timber cruise sheet notes a post at corner location. No references given. T.J. McLaren, 1952 through present, Notes on timber cruise sheet a 4" post and iron at section corner location and at S1/16 corner common to Sections 21 and 22. No references given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G9: A search was made for 4" post and iron at corner position. Iron has been lost to road maintenance. Remains of post was found near corner position. Established corner position by field survey. Found 1 5/8" axle shaft at South 1/16 corner between sections 21 and 22. Measured southerly from 1/4 section corner common to sections 21 and 22 to the South 1/16 corner and extended line southerly of South 1/16 corner the measured distance to set the corner position of G9. Measurements of the section line common to sections 21 and 22 agree very well in the North half and South half of the common section line. Found old blaze line to the west from the corner position. A search was made at GLO bearing tree positions, evidence has been lost. Corner position is accepted as a careful and faithful reestablishment of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G9: Set Berntsen Mon. no. A1NB30, stamped to identify corner position. Established the following reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ Alum. I.D. washers in the following reference trees. Cherry 7", S. 63 E., 54.83 feet, S27 BT ", Maple 11", N. 76 E., 123.53 feet, S22 BT ", W. Pine 6", S. 56 W., 44.33 feet, S28 BT ", W. Pine 8", N. 49 W., 45.71 feet, S21 BT ", Survey Marker sign on six foot steel post, N. 90 W., 8.0 feet. All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

