

Merrald W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-274

For corners in

Alger _____ Located in: _____ Corner Code # _____
(County)

1. Public Land Survey T 49N R 13W H1 _____
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILED
TIME 9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

COMMISSION

I, Robert L. Jamros, in a field survey on October 24, 1994, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H1: PLS-John Burt, DS, 1841, Set Qr. Section Post- W.Birch 3", N.14 E., 34 links, W.Birch 5", N.77 W., 38 links. CCI Forestry Division, Land and Timber Examination Report. T.J. McLaren, indicates 6" square post at corner position. 1949 through present. No references given. No other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H1: Began at BT corner of Sections 2 and 3, T.49N.,R.13W. Ran corrected compass line on a GLO bearing West to 40.0 chains and set a temp. point, found 3"sqd. post, down, located post point. Began at BT corner of Sections 3 and 4, T.49N.,R.13W. Ran corrected compass line on a GLO bearing East to 40.0 chains and set temp. point. Set temp. corner position at proportional location between temp. points. From temp. corner established GLO BT locations NW and NE. Found Birch remains in stump hole with bark flakes in NW position and a decayed Birch stump in the NE position. Established corner position from orig. BT remains of which falls southwesterly 4.4 ft. from temp. proportional corner position. Area is open and rolling with mixed timber.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H1: Set 2 1/4" Alum. Monument w/ 3 1/4" Alum. Cap stamped to I.D. corner position. Established reference trees w/ BT signs, blazed, scribed & painted. Set PK nails for measure w/ brass I.D. washers in the following reference trees. R.Pine 4", N.40 E., 28.57 feet, 1/4s BT", R.Pine 14", S.66 1/2 E., 13.29 feet, 1/4s BT", R.Pine 10", S.37 W., 54.40 feet, 1/4s BT", W.Pine 14", N.50 W., 30.44 feet, 1/4s BT", Steel witness post with Survey marker sign, S.75 W., 1.5 feet, All bearings are magnetic.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12 April 1995