

Approved by Alger County
 Land Survey Remonumentation
 Peer Group Under Act 345 of
 P.A. of 1990 On 5-19-1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-212

Robert L. Jamros
 Chairman
 For corners in

Alger (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>13W</u>	<u>H5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded May 26, 1994
 at 8:00 o'clock A. M., and
 Recorded in Liber 4 of Corner Rec.
 on Page 212
DeW. Hinesman
 Alger County Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5							●						
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on October 02, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H5: P.L.S. - Francis Coleman, DS, 1851. Set Or. Sec. post - Fir 12, N.42 W., 12 links. Beech 14, S.45 E., 23 links. C.C.I. Forestry, btwn. 1947 and 1968. Noted on Land and Timber Examination Report. BT Stump.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H5: Began at Southwest corner of Section at BT Section corner and ran East on a corrected compass line to 10.80 chains, no remains of Fir line tree. Continued on corrected compass line to 34.72 chains and found 24' Beech, a cruisers tally tree. Tally tree has face blazes on line and seven (7) axe notches on West side. Continued on corrected compass line to 39.66 chains and marked an area for search. Found 3 inch squared post down and decayed. From post point hole search locations for original BT's were spotted. Found remains of badly decayed Beech at Southeast position and at the Northwest location the Fir BT is no more than a stump hole with little or no decayed wood. Installed monument in post point hole and established new reference trees, and is accepted as a careful and faithful perpetuation of the position of the original corner. Corner lies in open mixed hardwoods.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H5: Installed 2 1/4" Aluminum monument w/ 3 1/4" Aluminum cap stamped to I.D. corner position. Est. reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. Beech 18", N.56 W., 22.96 ft., "1/4S-BT". Beech 10", N. 23 1/2 E., 46.45 ft., "1/4S-BT". Beech 12", S.60 1/2 E., 48.93 ft., "1/4S-BT". Maple 7", S.38 1/2 W., 8.16 ft., "1/4S-BT". Sur. Marker sign, N.61 E., 0.80 ft.

Signed by Robert L. Jamros Date 2 May, 1994
 Surveyor's Michigan License No. 25849