

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12-12-1995

RECORDING
MONUMENTATION

JAN 23 1996

COMMISSION
4-323

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REC'D and FILED

DEC 20 1995

2:45 p.m.

DONALD W. KINMUNEN, County Clerk
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

Chairman For corners in Alger <hr/> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>13W</u>	<u>H7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Jamros, in a field survey on July 06, 1995, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H7: PLS-Francis Coleman, OS, 1851, Set Qr. Section Post- Sugar 14", N.37 W., 23 links, W.Birch 12", S.10 E., 32 links. CCI Forestry Division, Land and Timber Examination Report. G.A. Moote, 1957, indicates a post at corner location. Department of Conservation, Billy D. Buckler, RLS, 1960, this corner was placed mid-way and on line between section corners. Set 1" iron pipe w/brass cap. References: W. Pine S.32 E., 80 links, Maple 7", S.13 W., 51 links., Filing No. 91, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H7: Began at BT section corner of sections 15,16,21 and 22 and ran corrected compass line on GLO bearing east. At 40.09 chains found 1 inch G.I.P. with 4 inch brass cap, Michigan Department of Conservation, stamped to identify corner position. Verified witnesses of the 1960 report to be in agreement with corner position. A search was made at GLO bearing tree positions, evidence has been lost. Corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H7: Stamped P.A. 345 in existing 4" Alum. capped Michigan D.N.R. Monument. Renewed existing reference tree w/ BT signs and paint. Established additional reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ Alum. I.D. washers in the following reference trees. Ex. Maple 10", S.17 W., 34.09 feet, "1/4s NBT", W.Pine 8", N.56 W., 23.15 feet, "1/4s BT", Maple 10", N.15 1/2 E., 36.95 feet "1/4s BT", Maple 6", S.34 E., 31.57 feet, "1/4s BT", Survey Marker sign on six foot steel post, N.21 W., 1.0 feet. All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

