

SURVEY & REMONUMENTATION

FEB 19 1998

Approved by Alger County Land Survey Remonumentation Peer Group Under Act 845 of P.A. of 1990 On 12-10-1997

SECTION

05-83

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

(County)	Located in:	Corner Code #
	49 13	H9
1. Public Land Survey	T <u>49</u> R <u>13</u>	<u>H9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED  
TIME 8:30 A.m.

DEC 17 1997

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on June 12, 1997, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H9: PLS - Francis Colman, DS, 1851, Set quarter section post - Sugar 14, N.53 E., 13 links, Sugar 8, S.16 W., 53 links \* No other subsequent restoration on record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H9: Located corner position by field survey \* Search in GLO position of N.53 E., 13 links fell in open graded area \* GLO position of S.16 W., 53 links fell on Eastern edge of runway for Burt Township Airport \* No old blaze lines in any direction from corner position evident \* Corner position was established on true line at the mid point between section corners East and West \* Corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H9: Set Berntsen Alum. monument no. A14820, stamped to identify corner position \* Established reference trees w/BT signs, blazed, scribed and painted \* Set PK nails w/Alum. I.D. washers for measure in the following \* Maple 12, S.81 E., 21.33 feet, '1/4S BT' \* Maple 7, S.38 E., 23.12 feet '1/4S BT' \* Maple 10, S.15 W., 29.58 feet, '1/4S BT' \* Survey marker sign on 6 foot steel post, East, 1.5 feet \* All bearings are magnetic.

Signed by Robert L. Jamros

Date 12/16/1997

Surveyor's Michigan License No. 25649

