

Approved by Alger County
and Survey Remonumentation
Peer Group Under Act 345 of
A. of 1990 On 4-8 1995

Gerald Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-273

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>13W</u>	<u>11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<u>SURVEY & REMONUMENTATION</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	<u>MAY 10 1995</u>
4. Lot No. _____, Recorded Plat _____		<u>COMMISSION</u>
5. Private Claims _____		

FILED
TIME 9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN
Register of Deeds Stamp & File Number

I, Robert L. James, in a field survey on October 24, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I1: PLS-John Burt, DS, 1841, Set Post Corner of Sections 2 and 3, W.Birch 2", N.38 E., 29 links, W.Birch 3", N.49 W., 35 links. PLS-Francis Coleman, DS, 1851, W.Pine 5", S.30 E., 7 links, Black Oak 4", S.72 W., 45 links., Subsequent restoration by author unknown. CCI Forestry Division, Land and Timber Examination Report, T.J. McLaren, indicates a 6' Square concrete block monument at corner position, 1949 through present. No references given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I1: Began at BT corner of Sections 1 and 2, T.49N., R.13W. Ran corrected compass line on GLO bearing West following old blaze line. At 37.73 chains and 6 ft. N. of line found dead and down 24" Pine with two notches and a blaze according to GLO survey instructions. GLO notes line tree at 37.52 chains, W.Pine 20". Continued West on corrected compass line following old blaze line. At 80.4 chains and 4 ft. N. of line found 6"x 6" square granite monument with "U.S.L.H.E." scribed on top and blaze lines East, West and North from monument. From existing monument established GLO BT locations NW and NE and found evidence of badly decayed Birch at both positions. Corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I1: Set 5/8"x 5" Rebar w/ 3 1/4" Alum. Cap stamped to identify corner position, drilled and grouted into the top of existing granite monument. Established reference trees w/BT signs, blazed, scribed & painted. Set Pk nails for measure w/ brass I.D. washers in the following reference trees. R.Pine 4", S.17 W., 19.79 feet, "S3 BT", B.Oak 8", S.45 E., 65.38 feet, "S2 BT", J.Pine 7", N.53 E., 57.28 feet, "S35 BT", B.Oak 8", N.76 W., 52.75 feet, "S34 BT", Steel witness post with Survey marker sign, S.66 W., 11.5 feet, All bearings are magnetic.

Signed by Robert L. James
Surveyor's Michigan License No. 25849

Date 12 April 1995