

Approved by Alger County
 Land Survey Remonumentation
 Peer Group Under Act 345 of
 P.A. of 1990 On 4-8 1995

Donald W. Carlson
 Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

4-281

For corners in

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>13W</u>	<u>I3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED
 TIME 9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert L. Jamros, in a field survey on October 21, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3									●				
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I3: PLS-Francis Coleman, DS, 1851, Set post corner of Sections 2,3,10 and 11, - Hemlock 8", N.27 W., 9 links, Fir 7", S.21 E., 16 links. A.C.R.C., H.H.Anderson,CE, 1935, Road alignment of Grand Marais East. Corner position noted by scale, 820 ft. N. of centerline of road. No references given. CCI Forestry Division, Land and Timber Examination Reports, T.J. McLaren, 1949, 6" square post at corner. No references given, AND Set post and iron, T.J.McClaren, 1963, Used measured distances from N directions to locate this cor., Could find no evidence of old Bearing trees. (old heavy burn), References: R.Pine 14", S.29 W., 4.9 ft., W.Pine 10", N.31 E., 12.5 ft., Robert L. Jamros, RLS, 1987, found 1" square steel bar next to 4" post., References: W.Pine 6", S.51 E., 24.4 ft., W.Pine 10", S.23 W., 23.5 ft., R.Pine 11", N.68 W., 12.7 ft., W.Pine 12", N.28 E., 13.1 ft., Recorded in corner record No. 3-358, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I3: Found corner position with 1" Square Steel Bar and 6" Post. Old blaze and paint lines extend N. and W., approx. 600 ft N. of County Road H-58 and approx. 200 ft. S.E. of Grand Marais Creek. Report of 1987 indicates 1" Square Bar measures well with other corners of the section. Found all bearing trees of the report of 1987 in excellent condition. Area is a open replanted Pine plantation. Existing corner position is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I3: Set 2 1/4" x 30" Alum. Monument w/ 3 1/4" Alum. Cap over top of existing 1" square steel bar. Stamped cap to identify corner position. Renewed existing reference trees w/ BT signs and paint., Set PK nails for measure w/ brass I.D. washers in the following reference trees. Ex. W.Pine 14", N.32 E., 12.92 feet, "S2 BT", Ex. R.Pine 10", N.64 W., 12.62 feet, "S3 BT", Ex. W.Pine 9", S.28 1/2 W., 23.39 feet, "S10 BT", Ex. W.Pine 7", S.47 E., 24.26 feet, "S11 BT", Steel witness post with Survey marker sign, N.45 E., 2.0 feet, All bearings are magnetic.

Signed by Robert L. Jamros Date 12 April, 1995
 Surveyor's Michigan License No. 25849