

SURVEY & REMONUMENTATION

FEB 19 1998

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 Ch. 12-10 1997

Donald W. Kinnunen
Surveyor

SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

05-81

For corners in _____ Located In: _____ Corner Code # _____
(County)

		49	13	I4	
1. Public Land Survey	T	<u>49N</u>	R <u>13E</u>	_____	_____
	T	_____	R _____	_____	_____
	T	_____	R _____	_____	_____
	T	_____	R _____	_____	_____
2. Property Controlling in Section	S	_____	T _____	_____	_____
	S	_____	T _____	_____	_____
3. Miscellaneous Property in Section	S	_____	T _____	_____	_____
	S	_____	T _____	_____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILED
TIME 8:30 Am

DEC 17 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. James, in a field survey on October 14, 1997, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I4: PLS - Francis Colman, DS, 1851 * Set quarter section post * Cedar 10, N.29 W., 30 links, Cedar 12, S.45 E., 10 links ***** T.J. McLaren, C.C.I. Co., Land Corner Records, 1963 * Set post and Iron * Could find no remains of original BT's * Witnesses - Cedar 12, N.52 E., 6.2 feet * Cedar 8, N.83 W., 3.5 feet * Unrecorded report. ***** No other subsequent restoration on record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I4: Located corner position by field survey * Position lies in low area East of Grand Marais Creek * Evidence of a paint line running East from corner position * Grand Marais Creek lies South of corner position approximately 235 feet, GLO calls for 218 feet * Found 4 inch squared post, S.48 W., 35.8 feet from corner position, and Iron of the 1963 unrecorded report was never found * Evidence at GLO original BT locations was not found. * Made search of area around corner position for remains of original post * Established corner position on true line at mid point between section corners North and South * Corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I4: Set Berntsen Alum. monument no. A1NB30, stamped to identify corner position * Established reference trees w/BT signs, blazed, scribed and painted * Set PK nails w/Alum. I.D. washers in the following - Balsam 5, S.09 E., 3.5 feet, "1/4S BT" * Cedar 12, N.33 E., 18.12 feet, "1/4S BT" * Cedar 12, N.25 W., 11.81 feet, "1/4S BT" * Cedar 14, S.57 W., 42.55 feet, "1/4S BT" * Survey marker sign on 6 foot steel post. N.34 E., 1.1 feet * All bearing are magnetic.

Signed by *Robert L. James*
Surveyor's Michigan License No. 25849

Date 12/10/1997

