

SURVEY & REMONUMENTATION

FEB 19 1998

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 845 of
P.A. of 1990 On 12-10-1997

Gerald W. Carter
Chairman

SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

05-80

For corners in _____ <small>(County)</small>	Located In:	Corner Code #	
	49 13	I6	
1. Public Land Survey	T <u> </u> R <u> </u>	<u> </u>	
	T <u> </u> R <u> </u>	<u> </u>	
	T <u> </u> R <u> </u>	<u> </u>	
	T <u> </u> R <u> </u>	<u> </u>	
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
3. Miscellaneous Property in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

FILED
TIME 8:30 AM

DEC 17 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on September 20, 1997, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15	●	14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

16: PLS - Francis Colman, OS. 1351, Set quarter section post - Sugar 10, N.27 W., 28 links * Sugar 9, S.39 E., 10 links * J.R. Radcliffe and G.A. Moots, G.C.I. Co., Land and Timber Report, 1957 * Indicate post at corner position **** No other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

16: Located corner position by field survey. Position lies in high open hardwoods * Found cruisers tally tree with blazes and hacks in all quadrants, N.54 E., 10 feet from located corner position. * Paint lines running North and West from corner position, no evidence of post found * Established corner position on true line at mid point between section corners North and South * Corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

16: Set Berntsen Alum. monument no. A1N830, stamped to identify corner position * Established reference trees w/BT signs, blazed, scribed and painted * Set 20 nails w/Alum. I.D. washers for measure in the following - Maple 4, N.29 E., 23.45 feet, '1/4S BT' * Maple 11, S.74 E., 25.77 feet, '1/4S BT' * Maple 6, S.18 E., 21.77 feet, '1/4S BT' * Maple 6, S.68 W., 17.75 feet, '1/4S BT' * Survey marker sign on 6 foot steel post, S.31 E., 2.0 feet * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25049

Date 12/10/1997

