

SURVEY & REMONUMENTATION

FEB 19 1998

Approved by Alger County Land Survey Remonumentation Peer Group Under Act 345 of P.A. of 1990 On 12-10-1997

SECTION

05-78

Gerald W. Jackson Chairman

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Located In:

Corner Code #

Table with 4 columns: Item, Located In (T/S), Corner Code #, and a blank column. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

FILED TIME 8:30 AM

DEC 17 1997

DONALD W. KINNUNEN REGISTER OF DEEDS ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. A dot is marked at row 8, column I.

I, Robert L. Jamros, in a field survey on June 17, 1997, 19, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

18: PLS - Francis Colman, DS, 1851 * Set quarter section post * White Birch 12, N.21 E., 37 links * Beech 12, S.54 W., 14 links **** R.J. Brotherton, RLS, C.C.I. Co., Land Corner Record, 1952 * Set 5 inch post * Corner was set on straight line between line trees of the Government Survey and field note distances and ties * Quarter corner set 40.285 chains from section corners * Witnesses - White Pine post 40, S.69 1/4 E., 1.23 chains (not found - 1997) * White Pine stump 24, N.38 W., 2.41 chains (not found - 1997) **** Billy D. Buckler, RLS, M.D. of C., Land Corner Record, 1960 * Set 1 inch iron pipe w/4 inch brass cap * Corner reestablished midway and on line between section corners * Witness - White Pine stump 36, S.75 E., 134 links * Recorded in Liber 2, Page 92, Alger County Corner Records. **** No other subsequent restoration on record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

18: Established corner position by field survey * Found White Pine stump remains 36, S.75 E., 134 links, monument has been lost * Exist. East-West track road has been widened and monument has been destroyed. * Evidence of paint or blaze lines not evident, area quite open with small amounts of timber. * Established corner position on true line at midpoint between section corners North and South * Corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

18: Set Berntsen Alum. monument no. A1NB30, stamped to identify corner position * Established reference trees w/BT signs, blazed, scribed and painted * Set PK nails w/Alum. I.D. washers for measure in the following - Maple 7, N.60 E., 59.35 feet, '1/4S BT' * Wild Cherry 3, S.49 W., 46.22 feet, '1/4S BT' * Wild Cherry 12, N.75 W., 51.79 feet, '1/4S BT' * Wild Cherry 12, N.28 W., 45.88 feet, '1/4S BT' * Survey marker sign on 6 foot steel post, S.75 E., 1.0 feet * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12/10/1997

